BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No:EE/YNK-D/E-PMT/03/2020-21 Dated: 24-07-2020

APPROVED TENDER SCHEDULE –'B'

Item 20

Name of Work :-Providing painting work to existing kerb stones,medians and benches at main and cross roads of ward no 04 of yelahanka Satellite town sub division

Sl	Description	Unit	Approved Qty	Rate quoted by the contractor approved rates Sri R RANGANATH	
				Rate	Rate in Words
1	KSRB M2100-10: Providing and laying in position plain cement concrete of Mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @ 0.89 cum and fine aggregates @ 0.46 cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centring complete as per specifications. (P. No-222, I. No-27.18)	Cum	15.00	5318.00	Five Thousand Three Hundred Eighteen Only
2	Providing and fixing pre cast solid cement concrete kerb stones out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation etc., complete as per direction of Engineer incharge.(P. No-27, I. No-5.30 of PW, P&IWTD SR 2018-19)	Nos	1111.00	423.00	Four Hundred TwentyThree Only
3	KSSRB 800-1: Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications. MORTH Chapter 8 P. No-180, I. No-24.1	Sqm	5550.00	82.00	EightyTwo Only

	Providing and Fixing pre cast covering Slab 100mm thick made out of CC 1:1.5:3 and jelly 20mm Down size with steel reinforcement including form work, curing, including form cost of all materials, labour, hire charges of Machinery, loading, unloading, laid and lift, transportation etc., complete. As per Engineer IN charge. (Data Rate).	Sqm	126.00	2292.00	Two Thousand Two Hundred NinetyTwo Only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.